

**Special Conditions****Construction Authorization**

The facility is an 546 acre sand and gravel pit, limestone quarry and processing plant designated as the Elmhurst Chicago Stone Company, Barber's Corners Plant, located in Sections 3 and 4, T37N, R10E of the 3<sup>rd</sup> P.M. in Will County, Illinois near Bolingbrook. Pit operations include the excavation of limestone and the excavation, crushing, screening, washing and stock piling of sand and gravel. Mine excavation operations shall maintain a minimum setback of 200 feet from potable water supply wells pursuant to Section 14.2 of the Illinois Environmental Protection Act. Operations result in the average discharge of 7.6 MGD (maximum 7.68 MGD) of pit pumpage and storm water runoff from Outfall 001 and the average discharge of 3.5 MGD (maximum 6.0 MGD) of pit pumpage and storm water runoff from Outfall 002 both to the East Branch of the DuPage River. A piping arrangement is located at Outfall 002 such that flow from Outfall 002 is directed to Outfall 002A to discharge into Bradlink Lake in order to maintain the water level in the lake during periods of dry weather.

Storm Water Pollution Prevention Plan: Authorization is hereby granted to construct treatment works and related equipment that may be required by the Storm Water Pollution Prevention Plan developed pursuant to this permit. Discharging sedimentation ponds are not covered under the Storm Water Pollution Prevention Plan authorization, unless they discharge to a non-coal outfall specifically identified in a construction authorization under this permit.

This Authorization is issued subject to the following condition(s).

- a. If any statement or representation is found to be incorrect, this authorization may be revoked and the permittee thereupon waives all rights thereunder.
- b. Plans and specifications of all treatment equipment being included as a part of the storm water management practices shall be included in the SWPPP.
- c. Any modification of or deviation from the plans and specifications in the initial SWPPP requires amendment of the SWPPP.
- d. Construction activities which result from treatment equipment installation, including clearing, grading and excavation activities which result in the disturbance of land area must meet the conditions of this permit.