

Special Conditions**Construction Authorization**

The facility is an existing, approximately 122 acre limestone quarry designated as Cessford Construction Company, Biggsville Quarry, located in Sections 17 and 18, T10N, R4W of the 4th P.M. in Henderson County, Illinois near Biggsville. Facility operations include the drilling, blasting, excavating, crushing, stockpiling and washing of construction aggregates and the production of agricultural lime products. Mine operations include removal of overburden which will be stockpiled for later use in reclamation or sold. Wash water, stormwater runoff and groundwater seepage are collected in a settling basin prior to discharge. Mine operations result in the pumped discharge of process wastewater, stormwater runoff and groundwater seepage from outfall 001 at an average discharge rate of 0.25 MGD to South Henderson Creek and the pumped discharge of process wastewater, stormwater runoff and groundwater seepage from outfall 002 at an average discharge rate of 0.25 MGD to an unnamed tributary of South Henderson Creek.

Storm Water Pollution Prevention Plan: Authorization is hereby granted to construct treatment works and related equipment that may be required by the Storm Water Pollution Prevention Plan developed pursuant to this permit. Discharging sedimentation ponds are not covered under the Storm Water Pollution Prevention Plan authorization, unless they discharge to a non-coal outfall specifically identified in a construction authorization under this permit.

This Authorization is issued subject to the following condition(s).

- a. If any statement or representation is found to be incorrect, this authorization may be revoked and the permittee thereupon waives all rights thereunder.
- b. Plans and specifications of all treatment equipment being included as a part of the storm water management practice shall be included in the SWPPP.
- c. Any modification of or deviation from the plans and specifications in the initial SWPPP requires amendment of the SWPPP.
- d. Construction activities which result from treatment equipment installation, including clearing, grading and excavation activities which result in the disturbance of land area must meet the conditions of this permit.
- e. For compliance with State law on threatened and endangered species, construction activities which may result in disturbance of woodlands shall be avoided between the dates April 1 and October 15 of any given year; trees may be cleared outside this date range. If the permittee desires to clear trees within this date range, the permittee shall seek an incidental take permit from the Illinois Department of Natural Resources.